

TURNKEY SIDING PROPOSAL

Customer: [REDACTED]
Lot: [REDACTED]
Subdivision:
Plan:

Date: 4 7 13
Salesman: Jeff W

Scope Of Work:

Hardie Soffit 12", 1x8 SPF Fascia and freeze and primed Crown- whole house
8 1/4 textured hardi, and hardie 4x8 with hardie 1x2 batton strips
double corners 5/4x4 and 5/4x6 primed spruce
Beaded plywood porch ceilings.
1x8 band with PVC drip cap.
4x4 bracket per plan
Standard ProBuild Housewrap.
4 columns included per plan
trim on 3 front windows included if needed
window/door install includes tape, shims, silicon
no deck or hand rail included

Siding Base Price:	\$9,365.00
House wrap:	\$840.00
window and 1 door install:	\$475.00
Total Siding:	\$10,680.00

[REDACTED] furnish all materials and labor necessary for completion of the scope of work. After plan review and sign-off, any alterations or deviations from the plan specifications involving extra cost of materials and/or labor shall be defined as a change order and will only be executed after negotiating the price for the changed work.

[REDACTED] is not responsible for lost or stolen material after installations, no [REDACTED] for damage from other sources. The customer agrees to provide safe access to the job at all times and the job site must be ready for installation by the agreed upon start date or schedule delays will occur. Additional charges may be added. [REDACTED] construction debris generated in the course of our installation and place it in a dumpster or other location on the job site as directed by the customer. Prices are good for 30 days.

The above price, specifications, and conditions are satisfactory and are hereby [REDACTED] work as specified and payment will be made.

Salesman Signature: _____ Customer Signature: _____
Date: _____ Date: _____